




APT Monthly Web Meeting

Updates from BAST
10.04.2025

APT at BAST

► Test sites



Indoor

Full scale pavement

length: 38 m (125 ft)
width: 7.50 m (25 ft)
depth: 3 m (10 ft)



Outdoor

duraBAST test area

6 test lanes with 100 m (320 ft) length
additional test fields/scenarios along 1 km (0.6 mi)

- surface monitoring approval
- bridge and tunnel research
- etc.



APT at BAST

▶ APT loading devices



Mobile Load Simulator MLS30

- 6.000 load repetitions at 50 kN wheel load per hour
- ~ 1 Mio. load repetitions per month
- Super Single tires or Dual Twin tires
- In operation since 2012



FastFWD as APT device

- 2.000 impulse loads at 50 kN per hour
- is currently being put into operation




Current projects – very short updates

- **Cold Asphalt Concrete with Bitumen Emulsion**
- **Foamed Bitumen and Fiber Optic Sensors**


Applying Cold Asphalt Concrete with Bitumen Emulsion (AC BE) as a base layer

- Application of the EN 13108-31 for development of an asphalt concrete with bitumen emulsion as a base course
- Proof of that through an APT program at duraBAST
- 4 cm SMA 11 S over **14 cm cold recycled layer (AC-BE)**
 - RA: 75% + 5-22mm VA: 8% + 0-2mm VA: 2% + 15% filler
 - 4.5% Bitumen emulsion** (C60B10, 60% bitumen 70/100),
 - 1% HRB class 4 (EN 13282-1)
 - OMC = 6%
 - ITS@5° = 1.05 MPa, TSR = 74%
- Construction: August 2023
- 1st APT section: 350.000 cycles
- 2nd APT section 1.000.000 cycles
- 3rd APT section: 600.000 cycles





Applying Cold Asphalt Concrete with Bitumen Emulsion (AC BE) as a base layer

Rutting (mm)



- High moisture in AC BE, production and construction → non-optimal mix
- The **FWD results** showed lower bearing capacity than expected (1 M.ESAL level)
- Permanent deformation** is an issue which should be considered in mix and structural Design
- For analytical structural design, appropriate material models & failure criteria should be developed

Bearing Capacity (SCI_{300})



Foamed Bitumen Surface Layer


FE 07.0320/2022/EGB



Quelle: https://www.wms.nrw.de/geobasis/wms_nw_dop

Foamed Bitumen Surface Layer

FE 07.0320/2022/EGB



Quelle: https://www.wms.nrw.de/geobasis/wms_nw_dop

Fiber optic sensors – on duraBASt

- ▶ Multiple FOS in 2 Layers with different lateral offset
- ▶ 8 cables, 80 m each
- ▶ blue= strain
- ▶ red= temperature
- ▶ Univ.-Prof. Dipl.-Ing.
Dr.techn. Werner
Lienhart, TU Graz


Institut für Ingenieurgeodäsie und Messsysteme (IGMS)

TU
Graz

Einbau

Deckschicht

- 2 Dehnungslängslinien
- 1 Temperaturlinie
- 1 Dehnungsmäander



Technische Universität Graz

20.02.2025

BASSt


5

Source: Einbau von verteilter faseroptischer Sensorik und Durchführung von Versuchen am duraBASt, Prof. Lienhart, TU Graz

Fiber optic sensors – on duraBASt



LKW-Zugmaschine Kennzeichen: GL BA 1001			
	links	rechts	Summe
vorne	3.050	2.800	5.850
hinten	1.350	1.350	2.700
Gesamtgewicht			8.550 kg
Abstand Prisma-Hinterachse 64cm			
Vito Kennzeichen: GL BA 1090			
	links	rechts	Summe
vorne	600	600	1.200
hinten	500	525	1.025
Gesamtgewicht			2.225 kg
Abstand Prisma-Hinterachse 64cm			



Source: Einbau von verteilter faseroptischer Sensorik und Durchführung von Versuchen am duraBASt, Prof. Lienhart, TU Graz

Quelle: https://www.wms.nrw.de/geobasis/wms_nw_dop

Fiber-optic sensor – on duraBASt


Institut für Ingenieurgeodäsie und Messsysteme (IGMS)



MLS in Betrieb

Messungen mit OFDR

- Dehnungen
- Frequenz 10 Hz
- Räumliche Auflösung 2.6 mm



Source: Einbau von verteilter
faseroptischer Sensorik und
Durchführung von Versuchen am
duraBASt, Prof. Lienhart, TU Graz

Technische Universität Graz

20.02.2025

BASSt

29



ERS – Electric Road Systems

- I. ERS with Asphalt**
(short teaser)


- II. ERS with precast concrete**
(detailed presentation)

Construction on duraBASt




Testing – power transfer

- ▶ Converted VW eCrafter
- ▶ Secondary coil under vehicle underbody, height adjustable
- ▶ Integration into the high-voltage traction network distribution
- ▶ Test speed up to 60 km/h with different lateral offsets




Testing – pavement properties

- ▶ Accelerated loading of the pavement (by use of MLS 30)
 - ▶ Loading on top of the coil and on top of the capacitor
 - ▶ About 300'000 loading cycles (5-to wheel load – eq. 10-to axle load)
- ▶ Repeated tests with FWD and Profilometer



Testing – pavement properties – FWD results

- ▶ Minor differences in deflection due to load between the composition. (load on capacitor, coil or reference)
- ▶ Indication of near-surface causes
- ▶ **Higher deflections are only caused by the load of the MLS 30 and not directly by the coils themselves.**





Testing – pavement properties – Profilometer

- ▶ Stationary measurements with uniform distances
- ▶ 1400mm measuring range
- ▶ Resolution approx. 0.1mm





- ▶ **Results: The deformations over coils are not significantly more pronounced than at the points without coils.**



Testing – pavement properties – 3D Scan

- ▶ 3D scans based on photogrammetry
- ▶ Resolution of <1mm over an area of 3.5m x 1m
- ▶ Exaggeration of the z-axis by a factor of 20
- ▶ False color representation for better visibility
- ▶ Deformation above the capacitors clearly visible





ERS with precast concrete

APT within the ERS R&D project “InductInfra”
10.04.2025 | Frederic Otto | BAST

Motivation for ERS

- ▶ Key challenges with BEVs
 - ▶ Limited range
 - ▶ Refueling / recharging time
 - ▶ Battery size
 - ▶ Required resources for battery production
 - ▶ Lack of sufficiently densified charging infrastructure
- ▶ ***One possible solution: ERS (Electric road systems)***

Types of ERS

Conductive

Overhead power line



source: <https://ehighway.hessen.de/>

Power rail



source: <https://infrastructureprojects.wordpress.com/2017/11/20/alstom-presents-aps-for-road-its-innovative-electric-road-solution/>


Inductive

Wireless (coils)



source: <https://www.enrx.com>

Inductive ERS / Wireless charging



Project „InductInfra“

- ▶ Funding: 11/2020 – 07/2024 by



on behalf of



Federal Ministry
for Digital
and Transport



- ▶ Consortium:



- ▶ Project goal: New construction concepts for the integration of wireless charging into the pavement structure

Project „InductInfra“

- Use of precast concrete modules




Project „InductInfra“

- Concept study and requirement analysis

**Systemic
requirements**

**Electrotechnical
requirements**



**Constructive
requirements**


**Requirements for
communication
and safety**

Prototype testing

Mechanical





Electromagnetic tests



Development of a demonstrator

- ▶ Full scale demonstrator at duraBASt (BASt Demonstration, Investigation and Reference Area)
- ▶ 50 m section with prefab modules
- ▶ 8 functional modules



Construction of the demonstrator

- ▶ Preparing the base layer and placing the modules




Construction of the demonstrator

- ▶ Complete the HF supply network and finalize the pavement structure



Construction of the demonstrator

- ▶ Setup of the control cabinet (power supply)



Finalized demonstrator




Testing – power transfer

- ▶ Test vehicle with trailer




Testing – power transfer – results

Stationary tests





Dynamic tests

(v = 50 km/h)




Testing – power transfer – conclusion

- ▶ Functional requirements fulfilled
- ▶ Power level within reasonable values throughout the whole test track
- ▶ Design potentials for optimization
- ▶ Estimated max. values (for two pick-up units):
 - ▶ 184 kW
 - ▶ Efficiency: 76 % - 82 %



Testing – pavement properties

- ▶ Accelerated loading of the pavement (by use of the MLS 30)
 - ▶ Loading of the joint area
 - ▶ 500'000 loading cycles (5-to wheel load – eq. 10-to axle load)
- ▶ Repeated tests with FWD and profilograph



Testing – pavement properties – visual results

Before loading




After 500 000 load cycles




Testing – pavement properties – FWD results

► Comparison of behaviour of loaded and unloaded joints



Location of FWD measurement:

- Loaded - center (red dashed line with circles)
- Loaded - east (orange dashed line with circles)
- Loaded - west (red dashed line with circles)
- Unloaded - center (green dashed line with circles)
- Unloaded - east (green dashed line with circles)
- Unloaded - west (green dashed line with circles)




Location of FWD measurement:

- Loaded - center (red dashed line with circles)
- Loaded - east (orange dashed line with circles)
- Loaded - west (red dashed line with circles)
- Unloaded - center (green dashed line with circles)
- Unloaded - east (green dashed line with circles)
- Unloaded - west (green dashed line with circles)

Testing – pavement properties – profilograph


- ▶ Relative movements at the joints

Transversal profile



● Longitudinal joint (east) ● Longitudinal joint (west)

Longitudinal profile



● Transversal joint (east) ● Transversal joint (west)


Testing – pavement properties – conclusion

- ▶ No visual damage detected
- ▶ Load bearing capacity lower than expected → still within reasonable magnitude
 - ▶ Important: the concrete modules are located between the wheel tracks!
- ▶ No critical joint movements could be detected
- ▶ Perspective of the construction crew: The construction concept is feasible and could be potentially applied on longer sections


Outlook – potential application on a highway

- ▶ Selection criteria: Structures (bridges, tunnels), protected areas, available power grids, traffic composition, potential areas for renewable energies, operating model

Example: A1 (10 km – Lower Saxony)



Example: A65 (4 km - Palatinate)



Legend

Study area

- Highway section
- Entrances and exits to the highway
- 1 km buffer around the highway section
- Substations
- High voltage grid
- Medium and low voltage grid
- Wind turbines
- Areas of potential

Thank you!

**We look forward to the
joint discussion.**

APT Program

Jan Ork

ork@bast.de

Dr. Mehdi Kalantari

kalantari@bast.de

Dr. Dirk Jansen

jansen@bast.de

ERS Research

Jan Ork

ork@bast.de

Dr. Frederic Otto

otto@bast.de

